

## 知 Test the link network quality between AP and AC

Wireless 龚训杰 2020-08-19 Published

### Problem Description

Test the link network quality between AP and AC

### Solution

```
[ac]dis wlan ap name uap verbose
.[40irf-probe]wlan ap-link-test
[40irf-wlan-ap-wa5620]tunnel latency-detect start
[40irf]display wlan ap name wa5620 tunnel latency
```

```
[ac-probe]WLAN ap-link-test 192.168.100.5
Transmitted packets      : 1
Received packets        : 1
Packet loss              : 0.00%
Transmitted packet length : 128
Received packet Length  : 128
Out-of-order packets    : 0
Min RTT(ms)             : 1
Average RTT(ms)         : 1
Max RTT(ms)             : 1
AP last reboot reason   : Power on
AP up time               : 0 weeks, 1 days, 21 hours, 34 minutes
```

```
[ac-wlan-ap-uap]display wlan ap name uap tunnel latency
AP name                  :uap
Tunnel Latency           :Enabled
Control Link Delay:
  Current Delay          :1ms
  Maximum Delay          :1ms
  Minimum Delay          :0ms
Data Link Delay:
  Current Delay          :1ms
  Maximum Delay          :1ms
  Minimum Delay          :1ms
```